SYSTEM SUMMARY- ROOFTOP ARRAY		
MODULE POWER	385	WATTS
TOTAL QUANTITY OF MODULES	1584	MODULES
MODULES PER STRING	18	MODULES
TOTAL QUANTITY OF STRINGS	88	STRINGS
TOTAL INVERTER CAPACITY	450	kWAC
TOTAL DC POWER RATING	609.8	kWDC
ARRAY TILT	10.0	DEGREES
ARRAY AZIMUTH- EAST	206.0	DEGREES
ARRAY AZIMUTH- WEST	225.0	DEGREES

CONCEPTUAL DESIGN
NOT FOR CONSTRUCTION

General Notes

- THIS DRAWING IS FOR CONCEPTUAL PURPOSES ONLY, NOT FOR CONSTRUCTION.
- THE PROPOSED ROW SPACING WILL PREVENT INTERROW SHADING ON DECEMBER 22ND FROM 10AM-2PM.
- ALL INFORMATION IS BASED ON GIS DATA, TO BE CONFIRMED WITH SITE SURVEY.

No.	Revision/Issue	Date
A	CONCEPTUAL SITE PLAN	09-05-2019

Firm Name and Address

Summit Ridge ENERGY

SUMMIT RIDGE ENERGY
1515 WILSON BLVD
ARLINGTON, VA 22209

Engineered By
M. GLASHEEN

Project Name and Address

MEADOWLANDS SOLAR

600 MEADOWLANDS DR
SECAUCUS, NJ

Project: MEADOWLANDS
Date: 9/5/2019
Scale: 1 IN = 60 FT
Sheet: C01
CONCEPTUAL SITE PLAN